



Kalayaan / Caliraya / Botocan HEPP Laguna, Philippines

This contract covered expansion works on the above mentioned 3 schemes.

It included detailed Engineering, Fabrication, Installation and Commissioning of:

- 7,000 tonnes of Penstocks and Steel Lining, Intake and Outfall Gates for Kalayaan.
- Radial gates and stoplogs with electrical control systems for the Caliraya Spillway.
- Rehabilitation of the cable (Skyway) car and derrick crane at Botocan.
- Fabrication was carried out in our own workshop on the construction site in Kalayaan.