



Xayaburi Dam HEPP Mekong River - Lao PDR

The Project consists of Design, Supply, Installation and Commissioning of 30,000 tonnes of Gates and Stoplogs.

- 7 x Surface Spillway Radial Gates 19m Span x 25m high.
- 4 x Low Level Outlet Radial Gates 12m span x 16m high.
- 1 x Maintenance Gate for the Lower Level Outlets.
- Upstream and Downstream Stoplogs.
- 3 x Sets of Navigation Lock Mitre Gates 14m span x 28m high.
- Water Feed System Bonneted Gates and Stoplogs.
- Fish Attraction System Bonneted Gates and Stoplogs.
- Power Intake Gates, Stoplogs and Trashracks.
- Pumping Station 1 and 2 and Auxiliary Powerhouse complete with Pumps, Gates, and Stoplogs.
- Fish Passing Facilities with over 70 Gates.
- Operation of the Navigation Lock and Spillway Gates up to Commercial Operation Date.

